

WKE LD parameter description



Model: WKELD10240

Power (w)	3800	Peak Flow (M ³ /H)	20
Inverter	5500	Lift (M)	40

Photovoltaic modules: 16 x 250Wp Poly in series

Model: WKELD10260

Power (w)	5300	Peak Flow (M ³ /H)	20
Inverter	5500	Lift (M)	60

Photovoltaic modules: 21 x 250Wp Poly in series

In the kit

Photovoltaic modules - Water pump - controller
Inverter - cabinet - electrical tape - water-proof
electrical tape - air switch - water level sensor
hanging rope - rope buckle - cables - MC4 Connector

Other power on request

WKE LD / DS

Model: WKEDS

Power (w)	100/4600	Peak Flow (M ³ /H)	0,30/20
Inverter	420/5000	Lift (M)	20/100

Photovoltaic modules: in funzione alla potenza

In the kit

Photovoltaic modules - Water pump - controller
Inverter - cabinet - electrical tape - water-proof
electrical tape - air switch - water level sensor
hanging rope - rope buckle - cables - MC4 Connector

Model: WKELD

Power (w)	2700/28000	Peak Flow (M ³ /H)	10/160
Inverter	5500/30000	Lift (M)	5/180

Photovoltaic modules: in funzione alla potenza

In the kit

Photovoltaic modules - Water pump - controller
Inverter - cabinet - electrical tape - water-proof
electrical tape - air switch - water level sensor
hanging rope - rope buckle - cables - MC4 Connector